


	A	B	C	D	E	F	G	H	I			
1	MATERIAL LIST											
2												
3	Project Name:	Cook Project					Species					
4							D	D		H	S	C
6	Contact:	Scott Lunsford					F	F		E	P	E
7	Tele:	530-216-5050					#	#	P	P	U	A
8				1	2	T	T	C	R			
9												
10												
11												
12	Item	Description	Quantity									
15	FRAMING											
16	VERTICAL GRAIN: (VG)											
17	11 1/2" X 11 1/2" POST		4/14'									
18	7 1/2" X 18' LARGE ARCH BASE- VG		4/5'									
19	7 1/2" X 14" LARGE ARCH TOP-VG		4/4'-6"									
20	7 1/2" X 16" SMALL ARCH BASE- VG		4/5'									
21	7 1/2" X 14" SMALL ARCH TOP- VG		4/4'									
22	7 1/2 X 7 1/2" TOP BEAM		2/14' 2/16'									
23	2 1/2" X 4 1/2" JOIST- VG		10/14'									
24	1 1/2" X 5 1/2" TENON		1/10'									
25	1 1/2" X 3 1/2" TENON		1/12'									
26												
27	*NOTE - ALL CEDAR TO BE UNITIZED TO ALLOW FOR AIR DRY											
28	-UNITIZE SO A 5K FORKLIFT WITH 48" FORKS CAN OFF LOAD											
29	-ALL UNITS MUST BE PLASTIC BANDED MIN 6 TIMES OVER OPAQUE PLASTIC											
30	- ALL MATERIALS TO BE CLEANED / WASHED PRIOR TO UNITIZING											
31	- ALL TIMBERS TO BE WAX AT THERE ENDS											
32	- ALL TIMBERS TO BE INSPECTED FOR QUALITY BEFORE UNITIZING											
33	- ALL LIKE SIZES PACKAGED TOGETHER AS A FORKLIFTABLE UNIT											
34	- INCLUDE DELIVERY TO COLUSA AS SEPARATE LINE ITEM											
35												
36	FASTENERS											
37	RED HEAD WEDGE ANCHORS 1/2" X 3.75"		1 BOX (25)									
38	WASHER FOR 5/8" BOLT			52								
39	5/8" X 3" PORTLAND SQUARE HEAD LAG BOLT			52								
40	HeadLOK STRUC WOOD SCREW 4.5" SPIDER DRIVE				1 BOX							
41	5/8" POPLAR WOOD DOWEL		4/48"									
42	3/4" POPLAR WOOD DOWEL		6/48"									
43	TITEBOND III BROWN INTERIOR EXTERIOR WOOD GLUE 16 OZ			1								
44	RAIN BUSTER 850	BROWN			2							
45												
46	STAIN & PAINT											
47	SIKKENS PROLUXE CETOL SRD (DARK OAK)		5 GALLONS									
48	MINERAL SPIRITS		1 GALLON									
49	RUST-OLEUM- OIL RUBBED BRONZED METALLIC		12 CANS									