


	A	B	C	D	E	F	G	H	I																																				
1	<b>MATERIAL LIST FOUNDATION &amp; FLOOR FRAME</b>																																												
2																																													
3	<b>Project Name:</b>	Espinoza Project				<table border="1"> <thead> <tr> <th colspan="6">Species</th> </tr> <tr> <th>D</th> <th>D</th> <th>E</th> <th>H</th> <th>S</th> <th>C</th> </tr> <tr> <th>F</th> <th>F</th> <th>U</th> <th>E</th> <th>P</th> <th>E</th> </tr> <tr> <th>#</th> <th>#</th> <th>C</th> <th>M</th> <th>R</th> <th>D</th> </tr> <tr> <th>1</th> <th>2</th> <th></th> <th>P</th> <th>U</th> <th>A</th> </tr> <tr> <th></th> <th></th> <th></th> <th>T</th> <th>C</th> <th>R</th> </tr> </thead> </table>				Species						D	D	E	H	S	C	F	F	U	E	P	E	#	#	C	M	R	D	1	2		P	U	A				T	C	R
Species																																													
D	D	E	H			S	C																																						
F	F	U	E			P	E																																						
#	#	C	M	R	D																																								
1	2		P	U	A																																								
			T	C	R																																								
4		6257 Himmel Street																																											
5		Paradise, Ca 95969																																											
6	<b>Contact:</b>	Scott Lunsford																																											
7	<b>Tele:</b>																																												
8		530-216-5050																																											
9																																													
10																																													
11																																													
12	<b>Item</b>	<b>Description</b>	<b>Quantity</b>																																										
15	<b>Concrete</b>																																												
16	Footing	6 Sack- 3/4" Rock- 3 Slump	30 Yards																																										
17	Isolated Footings	6 Sack- 3/4" Rock- 4 Slump	15 Yards																																										
18	Stemwall	6 Sack- 3/4" Rock- 4 Slump	30 Yards																																										
19	Front Porch Slab	6 Sack- 3/4"-3/8 Rock- 4 Slump	2 Yards																																										
20	Side Porch Slab	6 Sack- 3/4"-3/8 Rock- 4 Slump	1 Yard																																										
21	Garage Slab	6 Sack- 3/4"-3/8 Rock- 4 Slump	9.75 Yards																																										
22																																													
23		<b>Concrete Project Estimate</b>	<b>87.75 Yards</b>																																										
24																																													
25	<b>Gravel</b>																																												
26	Front Porch Area	3/4" Crush Rock	6 Yards or 9 Tons																																										
27	Side Porch Area	3/4" Crush Rock	6 Yards or 9 Tons																																										
28	Garage Area	3/4" Crush Rock	31 Yards or 47 Tons																																										
29																																													
30		<b>Gravel Project Estimate</b>	<b>43 Yards or 65 Tons</b>																																										
31																																													
32	<b>Foundation</b>																																												
33	#3 Rebar	3/8" - 20' Bar	85																																										
34	#4 Rebar	1/2" - 20' Bar	150																																										
35	2" Conc Dobie		250																																										
36	3" Conc Dobie		150																																										
37	15 Mill Vapor Barrier	Stego Wrap or Equal	900 Sq. Ft.																																										
38	15 Mill Vapor Barrier Tap	Stego Wrap or Equal	2 Rolls																																										
39	2x10 D.F. #2		230/16'																																										
40	2x4 D.F. #2	For Longer Wood Stakes and Kickers	60/16'																																										
41	18" Wood Stakes	Verify- Contractor	150																																										
42	24" Wood Stakes	Verify- Contractor	100																																										
43	36" Wood Stakes	Verify- Contractor	400																																										
44	Simpson SSTB24L HDG		13																																										
45	Siimpson CNW5/8	Oversize Threads	9																																										
46	Simpson SSW 18 x 9		2																																										
47	Simpson SSWAB1 x 36 HS		4																																										
48	Simpson AM5/8"	Verify- Contractor	165																																										
49	Simpson SSWTEL18		2																																										

	A	B	C	D	E	F	G	H	I
50	Simpson CBSQ46-SDS2			28					
51	Simpson WT8			400					
52	Simpson WT10			75					
53	Simpson W1			950					
54	Simpson BPS 5/8-3			150					
55	5/8" HDG Allthread		2/12" 3/18" 4/30"						
56	5/8" 14" Anchor Bolts	Galvanized With Hex Nuts		150					
57	Wire Tie	Pull Tier 8"	2 Bundles						
58	Tie Wire	Hand Tie	2 Rolls						
59	6" Felt Expansion Joint		160 LF						
60	Snap Cap Top	Match Felt Size	160 LF						
61	#8 Duplex Nails		50 Lb						
62	#16 Duplex Nails		50 Lb						
63	Duplex Screws 2 3/4"		15 LB						
64	Duplex Screws 1 5/8"		15 LB						
65	7 1/4" Marathon Blade			2					
66	Sawall Blades	Wood Metal- Longer Length	1 Pack						
67	Construction String 500'	Florescent Color	4 Rolls						
68	Upside Down Marking Paint	Florescent Pink	12 Cans						
69	Form Release	California Approved	15 Gallons						
70	Concrete Cure		10 Gallons						
71	4" DIA Metal Pipe x 6'	1/4" Wall- Garage Bollard -Galv		1					
72	4" Pipe Cap	Galvanized		1					
73									
74	<b>Floor Frame</b>								
75	2x4 PT D.F. #1		11/16'						
76	2x6 PT D.F. #1		25/16'						
77	4x6 PT D.F. #1		11/16'						
78	2x6 D.F. #2		20/16' 14/20'						
79	2x10 D.F. #2	Ribbon	11/20'						
80	4x6 D.F. Slec Struc	Girder	8/16'						
81	6x6 D.F. #2	Crunch Blocking	2/8'						
82	6x12 D.F. #1		1/12'						
83	3/4" T&G Plywood	High Grade Glue -for Weather	80 Sheets						
84	Redwood 6x14 Vents	1/4" Screen		20					
85	Simpson LU210			3					
86	Simpson AC6			48					
87	18" Ga x 12" Flashing	Bonderised	100 LF						
88	PL400 Sub Floor Glue	Large Size		32					
89	#8 Sinkers		100 Lb						
90	#16 Sinkers		100 Lb						
91	#16 Galvanized		25 Lb						
92	1 1/8" Teco Nails	Galvanized	15 Lb						
93	#8 Ring Shank Nails		10 Lb						
94	2" Senco Duraspin Subfloor collated Screw			4000					
95	7 1/4" Marathon Blade			2					
96	Sawall Blades	Wood- Longer Size	1 Pack						
97	3/4" Paddle Bit	6" min Long		4					
98	1 1/4" Paddle Bit	6" min Long		1					
99	Blue Chalk	Small Size		1					

	A	B	C	D	E	F	G	H	I
100	Red Chalk	Small Size	2						
101	Razor Blades	Utility Knife	1 Large Pack						
102	Carpenter Pencils		12						
103	Construction String 500'	Florescent Color	1						
104									
105									
106									